BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Estimate for Construction of Temporary Emmersion Tank for Lord Ganesh in Ward No. 06 Thanisandra Byatarayanapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	28.28	KSRB 2-1.1 : Earthwork in surface excavation in **ordinary soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1 **Page No. 6 / Item No. 2.1 of PWD SR 2018-19**	Cum	263.94	Rupees Two Hundred Sixty Three and Ninety Four Paise Only
2	214.50	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 **Page No. 143 / Item No. 19.1, PWD SR 2018-19 Up to 1.50 Mtrs Depth**	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
3	214.50	above 1.50 Mtrs Depth	Cum	172.25	Rupees One Hundred Seventy Two and Twenty Five Paise Only
4	945.00	Code 0516 - Providing Plastic Sheet **(Page No. XXIX / I. 755 PWD SR 2018-19**	Sqm	5.36	Rupees Five and Thirty Six Paise Only
5	165.00	Supply of water Through water Tank for filling Tank Hegadenagara	Each	360.00	Rupees Three Hundred Sixty Only
6	165.00	Rachenahalli	Each	360.00	Rupees Three Hundred Sixty Only
7	2.50	Providing Stone dust / Grit 4.75 mm to 0.075 mm to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 45 Code 400 metal Component **PWD SR Page No II PWD SR 2018-19 Rachenahalli Tank**	Cum	1000.00	Rupees One Thousand Only
8	2.50	Hegadenagara	Cum	1000.00	Rupees One Thousand Only
9	66.00	Hire charge of pumping water 3.5 KL/hr capacity Pump **Page No. L / Sl No. 49 PWD SR 2018-19 Hegadenagar**	Hrs	42.00	Rupees Forty Two Only
10	66.00	Rachenahalli	Hrs	42.00	Rupees Forty Two Only

11	154	Providing Causal Labours (Unskilled mazdoor Heavy) **(PWD SR 2018-19 Page No. LVI / I. 5) Hegadengara**	Nos	436.20	Rupees Four Hundred Thirty Six and Twenty Paise Only
12	154	Rachenahalli	Nos	436.20	Rupees Four Hundred Thirty Six and Twenty Paise Only
13	1600.00	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	Mtrs	65.00	Rupees Sixty Five Only
14	3300.00	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) Hegadenagar	Sft	8.00	Rupees Eight Only
15	3300.00	Rachenahalli	Sft	8.00	Rupees Eight Only
16	1650.00	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) Hegadenagara	Rft	17.00	Rupees Seventeen Only
17	1650.00	Rachenahalli	Rft	17.00	Rupees Seventeen Only
18	110	Hire Charge for Armless Plastic Chairs Hegadenagara	Nos	4.00	Rupees Four Only
19	110	Rachenahalli	Nos	4.00	Rupees Four Only
20	55	Hire Charge for Wooden Table of Size 6ft x 2ft Hegade nagara	Nos	40.00	Rupees Forty Only
21	55	Rachenahalli	Nos	40.00	Rupees Forty Only
22	660.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b) hegadenagara	Mtrs	9.00	Rupees Nine Only
23	660.00	Rachenahalli	Mtrs	9.00	Rupees Nine Only
24	55	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges **(PWD SR 2018-19 (P.LI / I.92) Hegadenagara**	Hrs	534.00	Rupees Five Hundred Thirty Four Only
25	55	Rachenahalli	Hrs	534.00	Rupees Five Hundred Thirty Four Only
26	66	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time Hegadenagara	Nos	285.00	Rupees Two Hundred Eighty Five Only
27	66	Rachenahalli	Nos	285.00	Rupees Two Hundred Eighty Five Only
28	6	Hire charges compoment name 1087 Crane charges **Page No. L Sl No. 66 PWD SR 2018-19** Lifting of Lord Ganesh Hegadenagara	Day	3390.00	Rupees Three Thousand Three Hundred Ninety Only

29	6	Rachenahalli	Day	3390.00	Rupees Three Thousand Three Hundred Ninety Only
30	11	1024 - Hire Charges of Tractor 50 HP including Operator and Fuel (P. XLVIII/I. 20) PWD SR 2018-19 Hegadenagara	Day	2129.00	Rupees Two Thousand One Hundred Twenty Nine Only
31	11	Rachenahalli	Day	2129.00	Rupees Two Thousand One Hundred Twenty Nine Only
32	220.00	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, **Page No. 7 / Item No. 2.10 / PWD SR 2018-19**	Cum	213.06	Rupees Two Hundred Thirteen and Six Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

" NIL CORRECTION NIC "
" DTS APPROVED

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.